

SECRET

OXC-2618
Copy 6 of 6

13 November 1961

MEMORANDUM FOR : Chief, Development Branch, Development Projects Division
SUBJECT : Status of Concrete Runway at OXCART []
REFERENCE : Memo from [] to C/DPD/DB, Dated 23 October 1961;
Subject: "Design Safety Factor for [] Runway" (OXC-2489)

25X1A

25X1A

25X1A

1. I have read with interest [] analysis of the runway situation [] and while I would agree that if in the last analysis we must increase the length of the bloody thing that we should do it sooner rather than later, I believe that to do it now might well be premature. Colonel Beerli shares this view, and additionally the weather, after first freeze, will prevent us from taking positive action until the spring.

2. My understanding is that at least in the testing of the J-75 version, and presumably even during a portion of the testing on the fully qualified engine, reduced vehicle loads will compensate for the increase in design weight. Then too in the operational phase, actual missions, I believe, are scheduled for launch in the night hours when the ambient temperature is well within reason. The only time you could really come close to violating the minimum safety factor would be in a maximum gross weight take-off under high ambient temperatures. Perhaps that will be the day when we do not attempt to fly unless we plan to sacrifice a portion of the [] in the manner [] has suggested.

3. As you know, runway length is always a compromise between a number of factors including gross take-off weight, thrust available, field elevation, ambient temperature, and the like. I certainly think that we should keep close watch on the gradual vehicle weight increase because if we do not, one of these days V_2 will be out beyond the end of the runway, and then we are in trouble. You are also aware that Kelly is very sensitive about people telling him that his head is up and locked on a matter of this sort. I would suggest that we quietly ask [] to have [] give us a cost estimate on

DOCUMENT NO. 8
NO CHANGE IN CLASS. X
DECLASSIFIED
CLASS. CHANGED TO: TS S C 25X1A
NEXT REVIEW DATE: 25X1A
AUTH: HR 70-2
DATE: 25X1A REVIEWER: []

25X1

SECRET

OKC-2618

Page 2

the order suggested by [] but that we do it quietly or []
[] will hear about it and then we will be in for the usual blast
from Kelly Johnson. I seem to remember that [] once told me that if
we added on to the present runway, we should figure on no less than
[] per 5,000 feet. In view of the fact that I believe the extension
would have to be at the southeast end, it might be a good idea if we got
the estimate and attempted to resolve the question before we installed
the runway lighting system. I also wish that you note the fact that any
extension to the southeast end would mean that the aircraft readiness pad
would end up being somewhere other than at the end of the runway. Colonel
Beerli is in agreement with my suggestion above, and I suggest that per-
haps you may wish to telephone this request for an estimate to []
shortly so that he will be in a position to bring it in with him when he
arrives 17 November.

SIGNED

JAMES A. CUNNINGHAM, JR.
Assistant Chief
DPD-DD/P

Distribution:

- 1 - C/DPD/DB
- 2 - ASST CH/DPD
- 3 - AC/DPD
- 4 - C/DPD/SPB
- 5 - DPD/DB
- 6 - DPD/RI

DPD-DD/P:JACunningham, Jr./mg

SECRET